



Cornerstone of Goa's Future  
23<sup>rd</sup> August 2019

NIQ -51

Ref.: GSIDC/Engg/Works/NIQ-/2019 - 2020/3386

### NOTICE INVITING QUOTATION

Sealed Item Rate quotations are invited from the eligible bidders for the work of "**Minor modification and miscellaneous works in GSIDC office**". The sealed quotations shall be received **upto 15:00 hours on 06<sup>th</sup> September 2019** and the same will be opened **at 15:30 hours on 06<sup>th</sup> September 2019**. The estimated cost for the work is **Rs.6,69,685.37**.

The Schedule of Quantities including the description of the item is furnished in **ANNEXURE-I** enclosed herewith. The bidders shall submit their offer by indicating rates for the item as per the enclosed **ANNEXURE-I** while submitting the quotation. Rates shall be exclusive of GST. All the pages of **ANNEXURE-I** shall be duly stamped and signed.

The quotation shall be accompanied by Earnest Money Deposit (E.M.D.) amounting to **Rs.13,500.00** (Rupees Thirteen Thousand Five Hundred only) in the form of Demand Draft from the Nationalised/Schedule Bank drawn in favour of GSIDC Ltd., payable at Panaji, Goa along with a covering letter, as per format enclosed at **ANNEXURE-II**, duly typed / handwritten, stamped and signed on the Letter Head of the bidder. The works are to executed considering approved make list placed at **ANNEXURE-III**. The quotation without accompanying the EMD in the specified format shall be summarily rejected.


Bidders in the field of similar work may peruse the Schedule of Quantities and obtain the same from the office of GSIDC on all working days free of cost in person or authorized representative only. The last date of issue of bid documents shall be **05<sup>th</sup> September 2019 upto 16.30 hours**.

The security deposit shall be collected by deduction from the bill at the rate of 5% and the Earnest Money deposited will be treated as part of Security Deposit. The Security Deposit shall be released on successful completion of 12 months from the date of completion of the work. The security deposit shall be released in full only all the required maintenance and/or repairs have been carried out by the Contractor in timely manner, to the complete satisfaction of the Engineer. In the event of failure of the Contractor to properly remedy the defects, the security deposit shall be released with appropriate deduction.

The work shall be completed within **45 days** from the date of issue of Letter of Acceptance / Work Order. In case of delay, the successful bidder shall be liable to pay

to the employer an amount of **Rs.1,790.00** (Rupees One Thousand Seven Hundred and Ninety only) per day as Liquidated Damages for default for every day. However, such total amount as Liquidated Damages shall not exceed 10% of the original quotation price.

GSIDC reserves the right to accept or reject any or all the quotations in part or full without assigning any reason whatsoever.

  
(Srinet Kothwale)  
Managing Director

Encl : Annexure-I and II

Copy to : 1. The Notice Board of GSIDC

2. **THE EXECUTIVE ENGINEER,** With a request to display the notice  
Public Works Department, on the Notice Board  
Works Division-I,  
Patto, Panaji -Goa:
3. **THE COMMISSIONER,** With a request to display the notice  
Corporation of City of Panaji, on the Notice Board.  
Panaji-Goa

GOA STATE INFRASTRUCTURE DEVELOPMENT CORPORATION LIMITED

ANNEXURE-I


 REFERENCE: NOTICE INVITING QUOTATION NO. **GSIDC/Engg/Works/NIQ-51/2019-2020/3386** Dated: 23<sup>rd</sup> August 2019

 PROJECT: **"MINOR MODIFICATION AND MISCELLANEOUS WORKS IN GSIDC OFFICE"**
**SCHEDULE OF QUOTATION**

<b>Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".</b>						
ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
<b>A</b>	<b>DISMANTLING &amp; DEMOLITION</b>					
1	Dismantling and Removing of tufted Glass partition with the frame work/beading patti and stacking within 50 meters lead as instructed by Engineer In charge	sq.mt	9			
2	Dismantling and removing of wooden flooring/Duroturf synthetic green matt and stacking the material within 50 meters lead as instructed by Engineer In charge	sq.mt	21			
3	Dismantling wooden boarding in linings of walls & partitions including supporting members of (50*50 mm size), wooden batten strip/granite stone (to be					

BIDDER

NO. OF CORRECTIONS



**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	stored without damaging), cement board on both side and stacking within 50 meters lead.					
b	Thickness above 19mm and upto 25mm (wooden boarding thickness)	sq.mt	20			
4	Dismantling false ceiling of all types suspended from structural component over sub frame of G.I or M.S at all levels including removing anchor bolts or screws drilled in walls ceilings etc including scaffolding and disposal of all unserviceable material at all leads and lifts as directed by Engineer	Sqm	10			
<b>B</b>	<b>CARPENTARY SECTION</b>					
5	Fabrication and installing in specified position <b>FULL HEIGHT STORAGE CABINET (FS-1) WITH SOLID SHUTTERS</b> of overall size of 860mm (L) x 600 mm (W) x 2100 mm (H) made up using 19mm and 6mm thk approved make BWR/BWP Marine grade plywood conforming to IS: 710 Exterior Grade, 1.0 mm thick laminate as per drawings with 1st class Indian teak wood beading patti including 3 or more coats of French polish for matching approved colour on all underside and	sq.mts	1.81			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	<p>unlaminated areas. The Storages cabinet shall be fitted with 02 equal size openable shutters fixed with total 10 nos of 75 mm length, 2.0 to 2.5 mm thick approved make /brand L / W Type hinges made up from solid extruded brass profiles &amp; 2 no D-shape s.s handles of 304 grade , Multipurpose 22 mm rim lock with two key Nickel plated and with levellers.The storage cabinet shall have one full height vertical partition &amp; 04 nos fixed horizontal shelf inside made up of 19 mm thick BWR/BWP Marine grade plywood as shown on the drawing with 1st class Indian teak wood beading patti on exposed sides. All exposed teak wood beading patti shall be provided with 3 or more coats of melamine polish of matching approved colour. All the required hardware and accessories to be installed as per Engineer's selection. (Quality of laminate shall be of price range of Rs 650 /- Sqm to Rs.700/- Sqm) Rate shall include of all iron mongeries hardware,fittings,fixtures etc. All material shall be of approved make. All works shall be completed as per the drawing/ Image, detailed technical specifications mentioned under VoL II and direction of the Engineer. (NOTE: elevation</p>					

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	area (two larger sides) will be considered for payment)					
6	Fabrication and installing at all heights in specified position <b>STAFF TABLE(C)</b> of overall size (860mm(W) x 610mm (D) x 750mm(H) made up using 19mm & 12mm thk approved make BWR/BWP Marine grade plywood conforming to IS : 710 Exterior Grade, 1.0 mm thick laminate as per drawings with 2nd class Indian teak wood beading patti including 3 or more coats of French polish for matching approved colour on all underside and unlaminated areas .The sides, back shall be in 12 mm thick . All exposed teak wood beading patti shall be provided with 3 or more coats of French polish of matching approved colour.The rate shall include all the required hardware and accessories to be installed as per Engineer's selection (Quality of laminate shall be of price range of Rs 650 /- Sqm to Rs.700/- Sqm) Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall be of approved make. All works shall be completed as per the drawing/ Image and direction of the Engineer. (Plan Area to be measured for payment)	sq.mt	1.1			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
7	Fabrication and installing in specified position OVERHEAD STORAGE OPEN RACK having Length upto 1000 mm, width 450 mm and height ranging from 800 -1000 mm fixed to wall /partition panel with necessary arrangements depending on site condition, at site made up using 19mm and 6mm thk approved make BWR/BWP Marine grade plywood conforming to IS: 710 Exterior Grade, 1.0 mm thick laminate as per drawings with 1st class Indian teak wood beading patti including 3 or more coats of French polish for matching approved colour on all underside and unlaminated areas. The storage cabinet shall have one full height vertical partition & one fixed horizontal shelf inside made up of 19 mm thick BWR/BWP Marine grade plywood as shown on the drawing with 1st class Indian teak wood beading patti on exposed sides. All exposed teak wood beading patti shall be provided with 3 or more coats of melamine polish of matching approved colour. All the required hardware and accessories to be installed as per Engineer's selection. (Quality of laminate shall be of price range of Rs 650 /- Sq.m. to Rs.750/- Sq.m.) Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall	sq.mts	1.1			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	be of approved make. All works shall be completed as per the drawing/ Image, direction of the Engineer. NOTE: Larger two sides will be considered for payment.					
8	Fabrication and installing in specified position FULL HEIGHT STORAGE CABINET WITH SOLID SHUTTERS with length upto 1000 mm overall width 450 mm and height upto 2100 mm made up using 19mm and 6mm thk approved make BWR/BWP Marine grade plywood conforming to IS : 710 Exterior Grade, 1.0 mm thick laminate as per drawings with 1st class Indian teak wood beading patti including 3 or more coats of French polish for matching approved colour on all underside and unlaminated areas. The Storages cabinet shall be fitted with sliding shutters fixed with necessary bearings arrangements of approved make /brand of required numbers, sliding door to be fixed with two recessed door handle 150 mm with locking arrangement with two key Nickel plated and with levellers. The storage cabinet shall have one full height vertical partition & 04 nos fixed horizontal shelf inside made up of 19 mm thick BWR/BWP Marine grade plywood as shown on the drawing with 1st	sq.mts	6.5			

BIDDER

NO. OF CORRECTIONS





**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	class Indian teak wood beading patti on exposed sides. All exposed teak wood beading patti shall be provided with 3 or more coats of melamine polish of matching approved colour. All the required hardware and accessories to be installed as per Engineer's selection. (Quality of laminate shall be of price range of Rs 650 /- Sq.m. to Rs.750/- Sq.m.) Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall be of approved make. All works shall be completed as per the drawing/ Image, direction of the Engineer. NOTE: Larger two sides will be considered for payment.					
9	Fabrication and installing in specified position OVERHEAD STORAGE CABINET WITH SOLID SHUTTERS having Length upto 2000 mm width 450 mm and height ranging from 800 -1000 mm fixed to wall /partition panel with necessary arrangements depending on site condition, fabricated at site using 19mm and 6mm thick approved make BWR/BWP Marine grade plywood conforming to IS: 710 Exterior Grade, 1.0 mm thick laminate as per drawings with 1st class Indian teak wood beading patti including 3 or more coats of French polish for matching	sq.mt	4.5			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	<p>approved colour on all underside and unlaminated areas. The Storages cabinet shall be fitted with 02 equal size openable shutters fixed with 75 mm length, 2.0 to 2.5 mm thick approved make /brand L / W Type hinges of required numbers made up from solid extruded brass profiles &amp; 2 no D-shape s.s handles of 304 grade and with levellers. The storage cabinet shall have one full height vertical partition &amp; one fixed horizontal shelf inside made up of 19 mm thick BWR/BWP Marine grade plywood as shown on the drawing with 1st class Indian teak wood beading patti on exposed sides. All exposed teak wood beading patti shall be provided with 3 or more coats of melamine polish of matching approved colour. All the required hardware and accessories to be installed as per Engineer's selection. (Quality of laminate shall be of price range of Rs 650 /- Sq.m. to Rs.750/- Sq.m.) Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall be of approved make. All works shall be completed as per the drawing/ Image, direction of the Engineer. NOTE: Larger two sides will be considered for payment.</p>					

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
10	Fabrication and installing in specified position MEDIUM HEIGHT STORAGE CABINET WITH SOLID SHUTTERS of width 410mm and height 1200 mm (length may vary as per site condition at site made up using 19mm and 6mm thick approved make BWR/BWP Marine grade plywood conforming to IS: 710 Exterior Grade, 1.0 mm thick laminate as per drawings with 1st class Indian teak wood beading patti including 3 or more coats of French polish for matching approved colour on all underside and unlaminated areas. The Storages cabinet shall be fitted with 02 equal size openable shutters fixed with 75 mm length, 2.0 to 2.5 mm thick approved make /brand L / W Type hinges of required numbers made up from solid extruded brass profiles & 2 no D-shape s.s handles of 304 grade , Multipurpose 22 mm rim lock with two key Nickel plated and with levellers.The storage cabinet shall have one full height vertical partition & one fixed horizontal shelf inside made up of 19 mm thick BWR/BWP Marine grade plywood as shown on the drawing with 1st class Indian teak wood beading patti on exposed sides. All exposed teak wood beading patti shall be provided with 3 or more coats of melamine polish	sq.mt	4.5			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	of matching approved colour. All the required hardware and accessories to be installed as per Engineer's selection. (Quality of laminate shall be of price range of Rs 650 /- Sq.m. to Rs.750/- Sq.m.) Rate shall include of all iron mongeries hardware, fittings, fixtures etc. All material shall be of approved make. All works shall be completed as per the drawing/ Image, direction of the Engineer. NOTE: Elevation area will be considered for payment.					
11	Providing and fixing of available wooden battens strips made up of compressed wood on new partition wall to match the existing elevation in Managing Director cabin with necessary arrangements, screws etc complete, as per the instruction of EIC. NOTE: wooden batten strips to be used from item no. 03 above in good condition.	each	10			
<b>C</b>	<b>PARTITION &amp; DOOR</b>					
12	Supply and installation at all level Partitions <b>(SOLID)</b> in full height upto false ceiling level made from 50mm X 50 mm X 2mm thick plain Aluminum box sections fixed vertically & horizontally at 600mm x 600mm c/c spacing with alternate vertical aluminium member anchored to	sq.mt	4.5			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	the ceiling slab and floor with the suitable fixing arrangement approved by Engineer including fixing 12mm BWP/BWR marine grade ply wood conforming to IS : 710 Exterior Grade on both sides of Aluminium grid work with suitable approved screws and infilling the cavity core of partition with approved ROCKINSUL RB SLAB of 50 mm thick having density 48kg /m3, NRC up to 1.05 including infill of hardwood material in the vertical aluminium member adjacent to the door opening in the partition etc complete. All Aluminium sections shall conform to grade 6063 T5 or T6 as per BS 1474 & shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat panelling , stainless steel screws etc,All works shall be completed as per the drawing/ Image and direction of the Engineer.					
13	Providing and fixing in specified position SINGLE <b>GLAZED PARTITION</b> with <b>available</b> 12 mm clear toughened float glass with polished edges fixed with S.S 304 GRADE U CHANNEL, 1.2 mm thick for 12 mm glass at top & bottom concealed in floor & ceiling including required m.s structural supports within false ceiling connecting to RCC supports	Sqm	2.2			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	including finishing glass to glass butt joints with clear silicone sealents etc complete. All works shall be completed as per the drawing/ Image and direction of the Engineer.					
14	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type (BWP), core of block board construction with frame of 1 st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: - 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	Sqm	2.2			
15	Providing and fixing brass hydraulic door closer of Everest Universal 68 or equivalent with necessary screws and fittings complete.	Each	1			
16	Providing & fixing Stainless Steel tubular lever D-Type mortise handles with round/Square nose, 24mm Mortise/sash lock body & Strike plate (all SS Finish), Pin cylinder 60mm with one side key and other side knob/thumb turn with necessary screws etc. complete	Each	2			
17	Providing & fixing 30x 6 mm thk 2nd class teak wood beading over flush door shutter at specified	Sqm	2.00			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	spacing and pattern using necessary fittings, hardware, adhesives etc complete as specified as shown in the drawings.					
18	Providing decorative Veneer 4mm thick of approved texture, colour shade & grain design and fixing with approved adesives , nails etc in specified pattern with or without cutting of grooves on wooden panelling on walls/ column /beam web/wooden structure, partitions, wooden false ceiling , architrave etc as shown in drawing including cost of adhesive of approved quality.etc comlete (Rate of Veneer shall be of price range of Rs 1200 /- Sqm to Rs.1300/- Sqm)	Sqm	15			
<b>D</b>	<b>FLOORING &amp; CEILING</b>					
19	Providing and fixing in approved brand /make 8 mm thick Calcium silicate board suspended false ceiling in horizontal / vertical surfaces, stepped, cove (straight & curvature) along with trap doors, consisting of G.I. Perimeter channel of size 0.55mm thick having one flange of 20mm and other flange of 30mm and a web of 27mm along with the perimeter of ceiling, screws fixed to brick wall / partition with the help of nylon sleeves and screw at 610mm centers. Then suspend G.I. Intermediate	Sq.m.	10			

BIDDER

NO. OF CORRECTIONS



**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	channels of size 45mm x0.9mm thick with two flanges of 15mm each from the soffit at 1220 mm centers with ceiling angle of width 25 x 0.55mm thick to soffit with G.I. cleat and steel expansion fasteners. Ceiling sections of 0.5mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm fixed to intermediate channels with connecting clips and in direction perpendicular to the intermediate channel at 457mm centers. Single layer 12.5mm thick HILUX board with tapered edge of size 1200mm x 1800mm is then screwed to the ceiling section with 25mm dry wall screws at 230mm centers.Finally boards should be jointed and finished with jointing compound paper tape to have a flush look which includes filling and finishing tile tapered edge of the board. The item also includes providing cutouts for electrical fixtures etc. Marking has to be provided for Sprinkler, Smoke Detectors etc. on the ceiling and also templates have to be provided and fixed in the ceiling made of 12mm BWR (boiling water proof) Plywood.numberte :- As laid (Gypsum surface area) area shall be measured for billing. All material shall be of approved make. All works complete as per the					

BIDDER

NO. OF CORRECTIONS





**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
	drawing, specification and direction of the Engineer.					
20	Providing and fixing Vinyl flooring of approved shade and design with adhesive complete in all respect.	sq.mt	21			
<b>E</b>	<b>PAINTING &amp; FINISHING</b>					
21	Wall painting (one or more coats) with plastic emulsion paint of approved brand and manufacture on old work to give an even shade.	sq.m	20			
22	Wall painting (two or more coats) with plastic emulsion paint of approved brand and manufacture on new work to give an even shade.	sq.m	20			
23	Applying one coat of primer of approved brand and manufacture on wall surface.	sq.m	20			
24	Providing and applying <b>white cement based putty</b> of average thickness 1.00mm of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sq.m.	20			
<b>F</b>	<b>MISCELLANEOUS WORK</b>					

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
25	Providing and fixing opaque film of make 3M/Garware or equivalent on glass internal partitions and doors as per approved sample ,design, drawing, specifications & direction of the Engineer/Architect with necessary glue, if required, labour,fixing in position etc.complete.	sq.mt	9			
26	Providing & fixing in position sunscreen roller blinds of make Vista/ Durian/Levolor/ Mac/Marvel/ Hunter Douglas or equivalent of approved color, shade of varying length, approved fabric with aluminum extruded rail powder coated in white. Control unit to be made of high strength reinforced plastic. Roller tube to be anodised extruded tube of high strength alloy, including all necessary fittings and fixtures like idler, head rail, control unit, roller tube, bottom rail, operating chain, fixing brackets, clamps, etc. complete. All works shall be completed as per the drawing/ Image and direction of the Engineer.	sq.mt	18			
27	Shifting of office furnitures (tables, chairs etc) from GMC section office to GSIDC office at 8th floor (within 12 km lead) and placing in position as per the direction of engineer in charge	Job	1			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
28	Shifting of dismantled items and furnitures from GSIDC office, EDC to GMC section office (within 12 km lead) and stacking the items as per the direction of engineer in charge	Job	1			
	<b>ELECTRICAL</b>					
29	Wiring for circuit/ submain wiring along with earth wire with the following size of FRLS PVC insulated copper conductor single core cable in the exisiting surface rigid PVC conduit / casing capping, as required.					
a	2 x 2.5 sq.mm + 1 x 2.5 sq.mm earthwire	Metre	137.96			
b	2 x 4 sq.mm + 1 x 4 sq.mm earthwire	Metre	72.55			
30	Supplying and erecting UPVC reinforced flexible conduit 25 mm in dia. conforming to I.S. with required number of couplings, PVC bushes, check nuts etc. complete.	Metre	83.50			
31	Supplying and fixing of following sizes of PVC casing capping along with accessories on surface as required. (a) 20mm casing capping	Metre	58.03			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
32	Supply and erecting rigid PVC conduit 25 mm dia with with PVC accessories on wall /ceiling as per specification	Metre	15			
33	Supplying and fixing modular switch/ socket on the existing modular plate and switch box including connections but excluding modular plate, etc. as required					
a	5/6 A switch Cat A	Each	22			
b	3 pin 5/6 socket outlet Cat A	Each	22			
34	Supplying and fixing following sizes modular PVC box alongwith modular base and cover plate for modular switches in recess as required					
a	6 Module Cat A	Each	11			

BIDDER

NO. OF CORRECTIONS




**Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".**

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE (RS.)		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
35	Supplying and fixing suitable size modular PVC box with modular plate and cover in front on surface or in recess including providing and fixing 1 no 6 pin 15/16 A modular socket outlet and 1 nos 15/ 16 A modular switch connection painting etc. as required. Cat A	Each	2			
36	Supplying and drawing/fixing indoor type 0.5 sq.mm FR PVC insulated copper conductor unarmoured telephone cable ITD/DOT approved, with GI saddles on wall or in the existing surface/recesed steel/PVC conduit having folowing pair(s), complete as required. - 2 Pair	Metre	260			
37	Supplying, installation and testing of suitable size modular box, modular plate and cover complete with RJ- 11 connector (modular telephone socket) including concealed metal box/ surface GI/ PVC box, modular plate, punching, identifying, complete as required. Cat B	Each	4			
38	Supplying, installing, testing and commissioning split type variable speed inverter technology room Airconditioning unit 1 TR capacity having ISEER minimum 3.50 to maximum 3.99 suitable to operate on 250V, 50 cycles, A.C. supply having 1 no. of air handling unit hi-wall mounting type	Each	1			

BIDDER

NO. OF CORRECTIONS



<b>Sealed Item Rate quotations are invited from the bidders for the work of "Minor modification and miscellaneous works in GSIDC office".</b>						
<b>ITEM NO.</b>	<b>DESCRIPTION OF ITEM</b>	<b>UNIT</b>	<b>QUANTITY</b>	<b>RATE (RS.)</b>		<b>AMOUNT IN FIGURES (RS.)</b>
				<b>IN FIGURES</b>	<b>IN WORDS</b>	
	complete with refrigerant R410A/R32 and copper condensor at position. specification no.APAC/SAC					
39	Supplying Pedestal fan 400 mm. 230 Volts 50 cycles oscillating type complete with guard and regulator 3 mtrs. of flexible wire and hand shield type 3 pin plug top.	Each	1			
40	Supplying, installing, testing and commissioning portable tower type room air conditioning unit of 1 TR capacity complete as required	Each	1			
<b>GRAND TOTAL</b>						
<b>GRAND TOTAL (IN WORDS) :-</b>						

NOTE: The rate shall be Exclusive of GST.

BIDDER

NO. OF CORRECTIONS



(Format of Covering Letter)

From :

-----,  
-----,  
-----.

Date :

To

**THE MANAGING DIRECTOR,**  
GSIDC Limited,  
7<sup>th</sup> Floor,  
EDC House  
Panaji Goa

Sir,

Sub : ***“Minor modification and miscellaneous works in GSIDC office”.***

Ref.: ***Notice Inviting Quotation No. GSIDC/Engg/Works/NIQ-51/2019-2020/3386  
Dated 23<sup>rd</sup> August 2019.***

In response to Notice Inviting Quotation No. GSIDC/Engg/Works/NIQ-51/2019-2020/3386 dated 23<sup>rd</sup> August 2019 for the aforementioned work. I / We hereby submit my / our offer by indicating rates for the item listed in the Schedule of Quotation enclosed at **ANNEXURE-I**. My / Our rates are exclusive of GST.

Demand Draft bearing No. \_\_\_\_\_ dated \_\_\_\_\_ amounting to Rs. 13,500.00 (Rupees Thirteen Thousand Five Hundred only) drawn on \_\_\_\_\_ Bank in favour of GSIDC Limited payable at Panaji, Goa is enclosed herewith as Earnest Money Deposit.

I / We hereby state that I / We fully abide by the conditions put forth in the said Short Notice Inviting Quotation.

Thanking you,

Yours faithfully,  
(Signature of the Bidder)

Full name of the Bidder : \_\_\_\_\_

Address : \_\_\_\_\_

Telephone No. : \_\_\_\_\_

Mobile No. : \_\_\_\_\_

Fax : \_\_\_\_\_

**ANNEXURE III**

**APPROVED MAKE LIST**

<b>Sr. No.</b>	<b>Item</b>	<b>Approved Makes</b>	<b>Remarks</b>
(1)	White Cement	JK, Birla	
(2)	Structural Steel	SAIL, Rastriya Ispat N L/VIZAG, TISCO/TATA, JSW, Ispat, Essar, Jindal to riva	
(3)	RHS/SHS Closed Structural	SAIL, Rastriya Ispat L/VIZAG, TISCO/TATA, JSW, Ispat, Essar	
(4)	Hi tensile black bolts	Guest Keen Williams (GKW), TVS (8.80 Grade)	
(5)	Welding Electrodes	Ador, Oerlikon, Esab, Adaani	
(6)	Precast Cement Products	Astra, Michael & Michael, Basant Batons, Dynamics, Pageant, Mallikarjun	
(7)	Construction Chemicals	Dr. Fixit (Pidilite), Mc-Bauchmie, Fosroc, BAL, Huntsman, Sika, GE, Hilti, Fischer, Dow Corning, MYKchomburg, Krishna Conchem, AppleChemie, Sunanda, Chokshi,	
(8)	Anchor Fasteners	Hilti, Fischer	
(9)	Wood Work (Marine Plywood, Flush Door, Block Board)	Greenply, Century Ply, Archid Ply, Anchor, National, Kenwood, Natural, Kitply, Orchid Ply, Dura Ply, Truewood, Prestige, Sonear, Euro, JK, Unitex	
(10)	FRP Doors	Om Venture, EP Kamat Group, Tuflite, Omega	
(11)	Pre-laminated board	Novapan, Acoboard, Archidlam, , Sonear, Greenply, Associate, Royal Touch, , Eco Boards, Anchor, Action Tesa	
(12)	Laminates/Flexy Ply/Veneer	Merino, Greenlam, Century, Formica, Green Ply, Archid, Decolam, Durian, National, Wilsonart, Homapal, Siblu, Optus, Marinolar, Century Lam, Mica, Merino, Anchor, Trijan, Kenwood, Natural, Duro Ply, Jaleram, Kitply, Jacson, AICA Sunimica	
(13)	Hardware Fittings	Ebco, Hettich, Casa, hafele, Polo/Kroma, Dorma, Ozone, Blum Drawer System, Grass, Godrej, Zipco,	



Sr. No.	Item	Approved Makes	Remarks
		Dorset, Saint Gobain, Yale, Kich, Everite, Enox, Neki, GKW/ Nettle Fold, Neterford, Pitroda, Renello, Ergo, Delco, Jaguar,	
(14)	Adhesives	Fevicol (S.H.), Araldite (Huntsman)/ Ciba Geigy, Aldrex, ICI	
(15)	Aluminium Section	Jindal, Indal, Hindalco, India Gypsum, Dorma Entramatic, Bhoruka	
(16)	Glass	Saint Gobain, Modi Guard, Asahowi, Dow Coney, Continental	
(17)	Special Effect Paint	Oikos, Matrix, Jotun	
(18)	Melamine Polish	Pidilite, ICI, Berger, Asian, Nerolac, Jottun	
(19)	Furniture ( Office and School Furniture)/Magazine racks/Newspaper stand	Godrej, Featherlite, Amardeep, Space & Style, Ravela, Wipro, BP Ergo, Durian, Methodex, Delite, Amber, Infinity, Neat Storage, Infiniti, <b>Nilkamal</b>	
(20)	Wood Preservatives	Wood Guard, Wood Case, Tremsil	
(21)	Locks / Locker Units	Vijayan, Golden Unit, Haffle, Hettich, Yale	
(22)	SS Plates, Tubes, Pipes & Rods/ SS Sheets	Jindal, TATA, SAIL, Salem	
(23)	Compactor	Godrej, Amardeep, Trinette, Kompres India, Methodex	
(24)	Wooden Flooring	Ergo, Pergo, Wood Floor, Konotex, Armstrong, Anchor	
(25)	Blinds	Vista, Durian, Levolor, Mac, Marvel, Hunter Douglas, Ferrari, Iris	
(26)	Textured Paints	Asian, Berge, Spectrum, Nitco, Oikos, Reinassance	
(27)	Frosting Film	Birla 3M, Garware, Llumar	
(28)	White Writing Boards/Notice Boards/Newspaper	White Mork, Alkosign, Altop, Ark,	

Sr. No.	Item	Approved Makes	Remarks
	Stand		
(29)	Carpet Tiles	Unitex, Mark, Equivalent	
(30)	Metal False Ceiling	Armstrong, Saint Gobain, Hunter Douglas	
(36) b	Acoustical Panelling & False Ceiling (Mineral Fibre/Gypsum/ Calcium Silicate)	Anutone, Hilux, Gypsum India, Aerolite, Envirotech	
(31)	Wall Clock	Titan, Quartz, Opal	
(32)	Projector Screen	Epson, Optoma	
(33)	Incinerator in Ladies Toilet	E. R. Ventures, Cecon	
(34)	P.V.C. Edge Banding	Rehen, Dolben of Germany	
(35)	Vinyl Flooring	Armstrong, Ego, Pergo, Wonder Floor, Hanwha	
(36)	Galvalume/ Zinalume Sheets	Tata, Bluescope, JSW	
(37)	Self tapping screws for roof	Corrodex, ITW, Corroshield, Roofex	
(38)	PVC Sheets	Finroof (Finolex), GE, Danpalon	
(39)	Mangalore Tiles	Albuquerque, Sun, C T Pai & Co, ohm tiles, Mangalore Tiles	
(40)	Aluminium Facade/ Aluminium Composite Panels	Hunter Douglas, Alucobond, Durobond, Durabuild	
(41)	Ceramic/Vitrified/Glazed Tiles / Fully vitrified Tac Tile	Endura, Durato, Somany, Spartek, Kajaria, Johnson, Nitco, Regent, Asian, Varmora, Orient Bell	
(42)	Precast Interlocking pavers	Basant Betons, Ultra, Spectra, Exflor, Dynamix, Pageant, SMG	
(43)	Glass Mosaic	Italia, Bisazza, Palladio	
(44)	Wall Putty	Birla Wall care putty, J.K.	
(45)	Cement Paint	Super Snowcem, Nitcocem	

Sr. No.	Item	Approved Makes	Remarks
(46)	Paints	Asian Paints, Nerolac, Berger, ICI, Sherwin Williams, Goa Paints, Nitco, Shalimar, J&N, Jottun, Akzonable, Setco, Spectrum, Oikos, Reinassance JCL, Jenson & Nicholson, Killick Nixon, Jotun	
(47)	Plumbing / Sanitary ware Fittings/Fixtures	Hindware, Parryware, Cera, Jindal, Zenith, TATA, zoloto, firtop, Airfield, Jaguar, Roca, Grohe, Moen, Neco, Finolex, Astral, Supreme, Prince, American Express, HansGrohe, TOTO	
(48)	Veneer	Kenwood, Anchor, Century, Greenply, Durian, Natural, Duroply, Trojan, Jaleram, Greenlam, ,National, Kitply, Archid,Jacson	
(49)	Aluminium Composite Panel	Alucobond, Durobond, Durabuild	
(50)	Carpets	Interface Carpets, India Carpets	
(51)	Zinc Oxide	Asian, Nerolac, Jottun	
(52)	Cooler cum Purifier	Eureka, Aquaguard, Blue Star	
(53)	Mattress & Pillow	Sleepeasy, Sleepwell, Duraflex, Kurlon, Restico	
(54)	Cavity Flooring	Titan, United Installation, DG	
(55)	Artificial Leather	Bhor, Baron, Stanley Leather, Spinney Beck	
(56)	Anti-Termite Treatment	Pest Control India Ltd.. Pest-O-Call	