

Ref: GSIDC/Engg/1393/NIQ- 99/2021-22/ 4517

9th November, 2021

NOTICE INVITING QUOTATION

Sealed Item Rate quotations are invited from the eligible bidders for the work of “**Design, casting & installation of Bronze Statue of Late Shri. Manohar Parrikar at Miramar**”. The sealed quotations shall be received *upto 15:00 hours on 16th November 2021* and the same will be opened after *15:30 hours* on the same day. The estimated cost for the work is **Rs.20,00,000.00 (Rupees Twenty Lakhs only)**.

The Schedule of Quantities including the description & procedure for executing the item is furnished in **ANNEXURE-I** enclosed herewith. The bidders shall submit their offer by indicating rates for the items as per the enclosed **ANNEXURE-I** while submitting the quotation. The Bidder shall include all the taxes as applicable in the rates quoted for various items specified in the bill of quantities except for Goods & Service Tax (GST) which will be paid as per the prevailing applicable rate during execution of work (if applicable). Bidders will ensure that full benefit of input tax likely to be availed by them is duly considered while quoting rate. All the pages of **ANNEXURE-I** and **ANNEXURE-II** shall be duly stamped and signed.

The quotation shall be accompanied by Earnest Money Deposit (E.M.D.) amounting to **Rs.40,000.00 (Rs. Forty Thousand only)** in the form of Demand Draft from the Nationalized / Schedule Bank drawn in favor of GSIDC Ltd., payable at Panaji, Goa along with a covering letter, as per format enclosed at **ANNEXURE-II**, duly typed / handwritten, stamped and signed on the Letter Head of the bidder. The quotation without accompanying the EMD in the specified format shall be summarily rejected.

A contractor having executed similar work may peruse the Schedule of Quantities and obtain the same from the office of GSIDC on all working days free of cost in person or authorized representative only. The last date of issue of bid documents shall be *15th November, 2021 upto 17:00 hours*.

Terms & conditions:

- The work shall be completed within 50 days from the day of issue of Letter of Acceptance/ Work Order.
- The Bidder shall acquaint himself with the site and scope of work before bidding for the work.
- The Defect Liability Period shall be **3 years (Three years)**
- Payment Terms: The payment schedule of Negotiated Financial Bid is mentioned at **Annexure III.**
- 5% Defect Liability Deposit will be retained for 3 years

GSIDC reserves the right to accept or reject any or all the quotations in part or full without assigning any reason whatsoever.



(Harish Adconkar)
Managing Director

Enclosure: **ANNEXURE-I, II and III**

GOA STATE INFRASTRUCTURE DEVELOPMENT CORPORATION LIMITED



REFERENCE: NOTICE INVITING QUOTATION NO. GSIDC/Engg1393/NIQ- /2021-22/ dated November, 2021

Project: "Design, casting & installation of Bronze Statue of Late Shri. Manohar Parrikar at Miramar".

ITEM NO.	DESCRIPTION OF ITEM	UNIT	QUANTITY	RATE		AMOUNT IN FIGURES (RS.)
				IN FIGURES	IN WORDS	
I	BRONZE STATUE Casting, Fabricating, Supplying, Polishing, Oxidizing, Painting & Installing/Fixing in position on given foundation base a Broze Statue of 8mm metal casting etc complete as directed by the engineer. Including all but not only limited to activies mentiojned below for total completion of the work: weight : 300- 400 kg. bronze material (85% copper, 8% zinc, 2% nickel, 2% tin, 2% mangnese)	JOB	1			
A	Identification, digitalization & finalization of exact posture by sketching out the details of the image, by scaling sizes of the body features as per the actual height of the subject person.					
B	Preparation & making of clay model for creating of form with fine tuning the features of the statue digitally & further providing with finishing touch with minute detailing to meet the exact feature & facial expressions of the statue image finalized for execution.					
C	Preparation & casting of model of 3mm or more thick glass fiber along with epoxy chemicals of approved make, glass fiber and marble powder as required, including further scrapping, cleaning, etc. to carve out the detailed features of the statue for further process					
D	Preparation & casting of model of bronze with required chemical or metal mixture of adequate percentage to attain the strength & to meet durability standards for warrantee period of 10 years (without external damage). The casting to be done in 3 pieces thus further joining the same with bronze metal followed by scrapping & cleaning the cast for clean, neat, seamless joint & smooth finish as desired. Including reinforcing internall with 16mm or more dia SS bar of 304 grade & keeping suitable length projection of SS bar to fix on the given foundation.					
E	Oxidization process to be carried out over the casted statue so as to avoid any corrosion and to keep the statue intact with suitable process including all thinghs required with 3 years warranty.					
F	Painting of the statue with duco paint process of required colour & texture and thickness with 3 years warranty.					
G	Transportation, handling & installation of the statue on site as dircted by the engineer on the given foundation including required material, tools & machinery for rigid fixing on the given foundation etc complete.					
GRAND TOTAL:-						
GRAND TOTAL (IN WORDS) :-						

Note:

1 Goods and Service tax shall be paid extra

Signature and Stamp

(Format of Covering Letter)

From:

Date :

-----,
-----,

To

THE MANAGING DIRECTOR,
GSIDC Limited,
7th Floor, Dr. Atmaram Borkar Road,
Panaji - Goa.

Sir,

Sub: "Design, casting & installation of Bronze Statue of Late Shri. Manohar Parrikar at Miramar".

Ref. : Notice Inviting Quotation No.GSIDC/Engg/1393/NIQ- /2021-22/dated November, 2021.

In response to Short Notice Inviting QuotationNo. GSIDC/Engg/1393/NIQ- /2021-22/ dated November, 2021 for the work of "**Design, casting & installation of Bronze Statue of Late Shri. Manohar Parrikar at Miramar**". I / We hereby submit my / our offer by indicating rates for the item listed in the Schedule of Quotation enclosed at **ANNEXURE-I**.My / Our rates are exclusive of GST applicable.

Demand Draft bearing No._____ dated _____ amounting to Rs._____(Rupees _____ only)drawn on _____ Bank in favour of GSIDC Limited payable at Panaji, Goa is enclosed herewith as Earnest Money Deposit.

I / We hereby state that I / We fully abide by the conditions put forth in the said Short Notice Inviting Quotation.

Thanking you,

Yours faithfully,

(Signature of the Bidder)

Full name of the Bidder : _____

Address : _____

Telephone No. : _____

Mobile No. : _____

Fax : _____

ANNEXURE III
MODE OF PAYMENT

Serial No	Description	Unit	In (%)
1	BRONZE STATUE Casting, Fabricating, Supplying, Polishing, Oxidizing, Painting & Installing/Fixing in position on given foundation base a Broze Statue of 8mm metal casting etc complete as directed by the engineer. Including all but not only limited to activies mentiojned below for total completion of the work: weight : 300- 400 kg, bronze material (85% copper, 8% zinc, 2% nickel, 2% tin, 2%	Job	
A	Identification, digitalization & finalization of exact posture by sketching out the details of the image, by scaling sizes of the body features as per the actual height of the subject person.	Job	15%
B	Preparation & making of clay model for creating of form with fine tuning the features of the statute digitally & further providing with finishing touch with minute detailing to meet the exact feature & facial expressions of the statue image finalized for execution.	Job	25%
C	Preparation & casting of model of 3mm or more thick glass fiber along with epoxy chemicals of approved make, glass fiber and marble powder as required, including further scrapping, cleaning, etc. to carve out the detailed features of the statue for further process	Job	20%
D	Preparation & casting of model of bronze with required chemical or metal mixture of adequate percentage to attain the strength & to meet durability standards for warrantee period of 10 years (without external damage). The casting to be done in 3 pieces thus further joining the same with bronze metal followed by scrapping & cleaning the cast for clean, neat, seamless joint & smooth finish as desired. Including reinforcing internall with 16mm or more dia SS bar of 304 grade & keeping suitable length projection of SS bar to fix on the given foundation.	Job	25%
E	Oxidization process to be carried out over the casted statue so as to avoid any corrosion and to keep the statue intact with suitable process including all things required with 3 years warranty.	Job	5%
F	Painting of the statue with duco paint process of required colour & texture and thickness with 3 years warranty.	Job	5%
G	Transportation, handling & installation of the statue on site as directed by the engineer on the given foundation inlcuding required material, tools & machinery for rigid fixing on the given foundation etc complete.	Job	5%
	Total		100%