



Offices of the Executive Engineer,  
Electricity Department, Division – XII, Xeldem, Quepem Goa.  
Ph: -2662646, 2662343, Fax: -2662343. Email: - exengr12@rediffmail.com

**BY SPEED POST/HAND DELIVERY**

No. EE-XII/Quot-16 (24-25)/ 1120 /2024-25

Date: 16 /09/2024.

To,

*h*  
*25/9*  
*00(TT)*  
*RE (best)*

Award No. :- 1296104  
Date :- 25/09/2024.  
SITE&C, 33 (HUP)  
Altinho, Panaji Goa. 26/09/24

**Sub:-**Quotation for work of Supply, Installation, Testing and Commissioning of 07 No. 2T Air Conditioning Units for Kiosks at 220/33KV Cuncolim Sub Station

The Executive Engineer Elect. Div-XII, Xeldem-Goa, on behalf of Governor of Goa invites you to offer your lowest rate for below mentioned work as per the terms and condition (Annexure-I) & (Annexure-II) enclosed here with:-

Sr No	Description	Unit	Qty	Rate	Amount.	Estimated Amount in figures exclusive of GST @18% in terms of ₹	Remarks/ Makes	
1	Supply of Split Air Conditioner confirming to IS: 1391 (part-2) as per enclosed specification (Annexure-II)	Nos.	07	45,442.71	3,18,098.97	3,18,098.97		
2	Supply and installation of suitable voltage stabilizer operating on single phase AC supply complete with time delay switch off reputed makes like Serval/V-Guard/ Everest.	Nos.	07	2372.88	16,610.16	16,610.16	MRA Makes: VOLTAS BLUE STAR/ CARRIE R/ HITACHI	
3	Providing and fixing of suitable stand for outdoor unit of 2TR split type air conditioner of TR capacity	Nos.	07	844.64	5,912.48	5,912.48		
4	Installation, testing and commissioning of cordless type high wall split type air conditioner of 2 TR capacity.	Mtrs	07	2612.99	18,290.93	18,290.93		
						<b>3,58,912.54</b>		
	<b>TOTAL AMOUNT RS. 3,58,912.54</b>							
	Percentage above (+ve)/ Below(-ve) in figures							
	Percentage above (+ve)/ Below(-ve) in words							
	At Par/ Same							
	Amount Quoted in Figure (exclusive of 18% GST)							
	Amount Quoted in Words (exclusive of 18% GST)							
	<b>E.M.D. Rs. 7,178/-</b> (Rupees Seven Thousand One Hundred Seventy Eight only)							
	Last date & time of receipt of quotation: 25/09/2024 upto 15:00hrs.							
	Date & time of opening of quotation: 25/09/2024 at 15.30hrs.							

*h*

Sealed quotation alongwith attached Terms and Conditions duly signed & super scribed on the top of envelop as "work of work of Supply, Installation, Testing and Commissioning of 07 No. 2T Air Conditioning Units for Kiosks at 220/33KV Cuncolim Sub Station". should be inserted in the quotation box kept at office of the Executive Engineer, Elect, Dept., Div-XII, Xeldem before Last date & time of receipt of quotation.

Name:

Signature:

Stamp of the Contractor:

Encl: As above



**EXECUTIVE ENGINEER-XII.**

Copy to:-

- 1) The Chief Electrical Engineer, Vidyut Bhavan, 3<sup>rd</sup> Floor, Panaji Goa. .... For information
- 2) The Superintending Engineer, Elect. Dept. Circle-I, Margao.... For information.
- 3) The Divisional Accountant, Accounts Section, Div-XII, Xeldem.... You is requested to be Present on the day of opening.
- 4) The Sub-Divisional Engineer, Elect. Sub-Div-I (EHV), Xeldem.
- ✓ 5) The Director of Information & Technology, IT HUB, 2nd floor, Altinho, Panaji-Goa .... With a request to publish the quotation called by this office for work of Supply, Installation, Testing and Commissioning of 07 Nos. 2T Air Conditioning Units for Kiosks at 220/33KV Cuncolim Sub Station".on Goa Govt. State portal by 23/09/2024.
- 6) O/c





## ANNEXURE-I

### TERMS & CONDITIONS

- 1) **RATES**: The rates quoted should be firm & for Supply & Erection at Xeldem Sub-Station.
- 2) **TAXES & DUTIES**: The rates quoted shall be inclusive of GST, transportation, octroi, levies, packing & forwarding etc.
- 3) **VALIDITY**: The rates quoted shall be valid for a period of 60 days from the date of opening of quotation.
- 4) **COMPLETION PERIOD**: work of Supply, Installation, Testing and Commissioning of 07 No. 2T Air Conditioning Units for Kiosks at 220/33KV Cuncolim Sub Station shall be completed within 30 days from the date of placement of order.
- 5) **EARNEST MONEY DEPOSIT**: An amount of Rs. 7,178/- towards **EARNEST MONEY DEPOSIT** shall be furnished by demand Draft drawn from any scheduled bank guaranteed by Reserve Bank of India, payable at Quepem in favour of the Executive Engineer, Div XII, Electricity Department, Xeldem-Goa in the envelope marked as "Envelope A". The said envelope should be stapled to the quotation/offer enclosed in a separate envelope marked as "Envelope B" with the enquiry reference no superscribed on it. The quotation received without EMD will be summarily rejected.  
The Government shall without prejudice to any other right or remedy, be at liberty to forfeit 50% of the EMD, if any quotationer, whose quotation is accepted fails to commence the work/supply specified in supply specified in supply order within the prescribed time or abandons the supply before its completion.
- 6) **PERFORMANCE SECURITY**: Performance Security of 5% of the ordered value shall be deposited with this office on issue of acceptance letter & the same shall be refundable on completion of the work & recording of the completion certificate.
- 7) **SECURITY DEPOSIT**:- Security Deposit amounting to 2.5% of the ordered value will have paid by you or the same shall be deducted from the bills after adjusting the EMD paid by you. The Security Deposit will be retained till the expiry of the guarantee period & thereafter the same shall be refunded against an application in Form-28, subject to the condition that defects in the material noticed during the guarantee period will be replaced by you at your own cost to the entire satisfaction of the Engineer-in-charge and on the recovery of any amount due to the Government. recovered from you will be refunded after the expiry of the guarantee period on receiving written request from you however, if any recovery is to be made from you for sub-standard material, short supply etc., or any other reason against this order, the same will be recovered from this security deposit amount.
- 8) **PAYMENT**: Payment will be made only after supply of material in full & good condition and on acceptance by Engineer-in-charge. The contractor shall indicate Income Tax, Pan Number & TIN Number registered with the Collectorate of Custom & Central Sales Tax in the invoices/receipt, Bank a/c No., Name of Bank, IFSC code, MICR code, mobile No., e-mail address etc. for e-payments without which payment will not be released.
- 9) **CONTRACT CONDITION**: Orders will be governed by the conditions of P.W.D. agreement **Form No.10**. Your acceptance for the same should be confirmed.
- 10) **COMPENSATION**:- For all the late supply of material, a compensation at the rate of 1% of the order value per day of delay in completion beyond the schedule delivery date mentioned above but not exceeding 10% of the order value will be charged.
- 11) **GUARANTEE**: The Supplied Materials will have to be guaranteed for satisfactory performance the period of 12 months from the date of Supply.
- 12) **THE RIGHT TO REJECT**: The right to reject any or all the quotations, without assigning any reasons shall rest with the undersigned.
- 13) **DATE OF RECEIPT AND OPENING OF QUOTATION**: The quotation will be received up to 15.00hrs on 25/09/2024 and it will be opened at 15.30 hrs on the same day.

*[Handwritten signature]*

*[Handwritten signature]*

Executive Engineer,  
Div XII – Xeldem.

**ANNEXURE-II (GTP)**

1	<p>Supply of Split Air Conditioner confirming to IS: 1391 (part-2) 1992 with AMD No.1 to 4 conformation to the enclosed (Annexure-II) specification:</p> <p>(a) Type: High wall mounted split type air conditioner.</p> <p>(b) Capacity 2TR capacity with remote control consisting of indoor and outdoor unit standard copper pipe for suction with installation and copper pipe for discharge with insulation, having built in time delay features, auto start facility, three speed cooling capacity, oscillating louvers with rotary compressor, L.C.D. display on board and cordless remote.</p> <p>(c) Star rating: BEE 3 star and above</p> <p>(d) Air circulation: 900 m<sup>3</sup>/hr</p> <p>(e) Refrigerant: HCFC R-22</p> <p>(f) Auto air swing: 4 way</p> <p>(g) Operating voltage: 230 V AC, 50Hz, 1ph</p>
2	Supply and installation of suitable voltage stabilizer operating on single phase AC supply complete with time delay switch off reputed makes like Servel/ V-Guard/ Everest.
3	Providing and fixing of suitable stand for outdoor unit of 2TR split type air conditioner of TR capacity
4	Installation, testing and commissioning of cordless type high wall split type air conditioner of 2 TR capacity.



**EXECUTIVE ENGINEER-XII**